TYPICAL QUANTITIES FOR

SHADOWFIX AND X-TACK INSTALLATIONS

Fixing Type:	ShadowFIX with X-Tack	X-Tack only
Tongues	2 strips / sheet (plus extra for areas where ceiling meets wall)	
Screws	5 screws / tongue	
Toggles	Minimum 3 toggles	
X-Tack Adhesive	1 tube / 2 sheets	1 ½ tubes / sheet
Cartridge Gun (1:18)	At least 1	At least 1
Foam Cleaner	1 can / 20 sheets	1 can / 10 sheets (timber frame)
Tec7 Cleaner		1 can / 10 sheets (metal, top hat, frame)
Router Bit	For any on-site edge re-grooving	
Touch Up Treatment	For re-sealing of any on-site cut edges	For re-sealing of any on-site cut edges

* ShadowFIX is only available for 12.5mm Ariaply and iHoop panels.

* The quantities above are typical amounts – please call us on 07 3426 8666 to discuss the specifics of your particular installation.